



Quant. Symbol Type of Lighting Unit

5  Existing 5m concrete column with 35w SOX lantern. To be taken up and removed to recycle.

Quant. Symbol Type of Lighting Unit

4  Proposed 6 metre tubular steel column with spigot mounted bottom entry Urbis Ampera Mini 24LED Neutral white 5141-500mA lantern unit 336612. Factory set dimming regime 1(22:00-5:30 50%). Finished in grey.

Notes:

1. All new columns to have Osram drivers with factory set dimming regime 1.
2. Existing services detailed on this drawing are not to be treated as accurate. The contractor is responsible for proving all services on site prior to the commencement of works.

City of Bradford MDC www.bradford.gov.uk Department of Regeneration Strategic Director: Barra Mac Ruairi FRBA FRSA	Design Office Transportation and Highways Service Street Lighting Unit Wakefield Road Depot Foundry Lane Bradford BD4 7NW	Project THE GROVE SHIPLEY Client CAP 16/17	Design	Drawn	Checked	Released	Drawing Title STREET LIGHTING PROPOSALS Drawing No. R/PTH/SL/100146/15207-1A
			Scale(s) @ A3	Approved	Date	CBM	
			1:500	A Preece	JUN 16	CBM	
Revision			CBM	JUN 16	Engineer to Contract		
			Inits	Date	C P Leach BSc C.Eng MICE DMS		