



Quantity	Symbol	Type of Lighting Unit
37		Proposed 8 metre Steel column with Spigot Mounted lantern with NEMA socket and 48 LED lamp Urbis Amper midi, 5140, 48 LED, NW @ 500mA dimmed to level 1
15		Existing 6 metre Steel column with Spigot Mounted lantern and 55w SOX lamp To be removed and taken down to tip for recycle
21		Existing 6 metre Concrete column with Spigot Mounted lantern and 55w SOX lamp To be removed and taken down to tip for recycle
1		Existing 12 metre Steel column with 1.25 metre projection bracket, Side Entry lantern and 250w SON/T lamp To be removed and taken down to tip for recycle

A	Original		MK
Revision		Inits	Date
City of Bradford MDC			
www.bradford.gov.uk			
Department of Regeneration Strategic Director: Barra Mac Rualri RIBA FRSA			
Design Office Transportation and Highways Service Street Lighting Unit Wakefield Road Depot Foundry Lane Bradford BD4 7NW			
Project SPRING GARDENS LANE KEIGHLEY			
Client CAPITAL REPLACEMENT 2016-17			
Engineer to Contract C P Leach BSc C.Eng MICE DMS			
Design MK	Drawn MK	Checked KAO	Released MK
Scale(s) @ A1 1:500		Approved A Preece	Date
Drawing Title STREET LIGHTING PROPOSALS			
Drawing No. R/PTH/SL/100146/15196-2A			